



CAST ALUMINUM SIGN WITH SCROLLS CAN BE ORDERED WITH BLACK, WHITE OR GOLD HELVETICA OR BRUSH SCRIPT VINYL NUMERALS. SPACE AVAILABLE FOR NUMERALS IS 2" X 8".

CAST ALUMINUM POST CAP AND FINIAL ASSEMBLY.

CAST ALUMINUM BRACKET ASSEMBLY.

S.ST'L. SCREWS ARE SUPPLIED TO ATTACH MAILBOX ASSEMBLY TO POST.

CAST ALUMINUM MAILBOX ASSEMBLY.

MAILBOX HOLDER CONSISTS OF CAST ALUMINUM MOUNTING PLATE WELDED TO CAST ALUMINUM ARM WITH SCROLL.

350-6'6" 3" DIA. ALUMINUM TUBING X .125" WALL.

2 PC. CAST ALUMINUM WRAP AROUND BASE WITH S.ST'L. FASTENERS. (139-3 SHOWN)

CUSTOMER MUST CONCRETE POST IN GROUND. CONCRETE FOOTER TO BELOW LOCAL FROST LEVEL OR LOCAL CODE.

1/2" SCH. 40 ALUMINUM PIPE X 7" LONG HORIZONTAL STABILIZER ROD.

STANDARD MAILBOX SHOWN. OTHER POST CAPS, POSTS AND WRAP AROUND BASES AVAILABLE-CONTACT FACTORY.

NOTE:
BEFORE MOUNTING MAILBOX AT HEIGHT SHOWN ABOVE, PLEASE CHECK WITH YOUR LOCAL POSTAL SERVICE FOR THEIR REQUIRED MOUNTING HEIGHT.

HEIGHT	57 5/8"
WIDTH	25 1/8"
PROJECTION	
TOP TO OUTLET	

Drawing for illustration only - scale approximate

<p>330 KENDAL LANE HANOVER, PA 17331 PH (717) 638-8884 - FAX (717) 638-8039</p>	TITLE: "PINE VALLEY" CAST ALUMINUM MAILBOX WITH SIGN AND SCROLL	
	SCALE: 1=8	DATE: 04/21/05
		DWG. NO. M144S